

# SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON  
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>52</u> R <u>39</u>		L-3
	T _____ R _____		_____
	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____

Recorded November 16 1994  
at 1:20 o'clock P. M. in  
Liber 3 page 218  
*J. E. Masley* Deputy  
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

$\frac{1}{4}$  Corner, Section 1 & 12, T52N R39W

Earl W. Applekamp, in a field survey on September 03, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3												●	
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Corner established by William A. Burt, U.S. Deputy Surveyor in September 1845. Set Hemlock post.

Original bearing trees:

Hemlock	22"	N35°E	43 Links	(28.38')
Maple	14"	N28°W	20 Links	(13.20')

**ONTONAGON COUNTY**  
**PEER APPROVED**  
*E. W. Applekamp*  
ONT Co. REP  
9-14-94

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

No original evidence found. A map dated 5-15-74 by R.S. Scott Engineering Co. Inc., showing the proposed Lake Shore Drive road identifies an existing 1" pipe at Station 23+01.52 with ties East and West.

In August 1976 a survey by Earl W. Applekamp, P.S. set a  $\frac{1}{2}$ " iron pin with cap at this location. The road was built and had a 3 foot lift. I established the following monuments.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I set 2 Reference Monuments on line. One West 54.69 feet East 54.96 feet. Both monuments are  $2\frac{1}{2}$ "x30" aluminum pipe cap stamped to read: County Monumentation,  $\frac{1}{4}$ , S-1, S-12, T52N R39W 1994, P.S. 17610. The corner position is marked with a  $\frac{1}{2}$ " iron pin with plastic cap below the blacktop. I established the following bearing trees:

14" Cedar	S61°W	66.94 feet
5" Cedar	S75°E	55.40 feet



Signed by *Earl W. Applekamp* Date September 03, 1994  
Surveyor's Michigan License No. 17610

218