

SURVEY & REMONUMENTATION

APR 26 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970



For corners in

<u>ONTONAGON</u>	Located In:	Corner Code #
	39	<u>M-2</u> ✓
1. Public Land Survey	T 52 R 39	A-2
	T 52N R 38W	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Recorded October 19 1994
at 2:13 o'clock M.
Liber 3 page 212
Julie Maskey Deputy
Register of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1/4 Corner Section 1 & 6, T52N R38W & R39W

Earl W. Applekamp in a field survey on September 15, 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Alder Post			
Fir	S50°E	16 Links	(10.56')
Sugar	S85°W	16 Links	(10.56')

ONTONAGON COUNTY
PEER APPROVED
Earl W. Applekamp
Ontonagon Co. Rep.
10-12-94

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The corner was set by single proportionate measurement between the NE and SE corners of the Section. The corner position is in agreement with the call to the Firesteel River. A permanent monument was set at the position described below.

Research on file with County Remonumentation Representative



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 1/2" x30" long aluminum pipe with a 3 1/4" cap, stamped to read: County Remonumentation 1/4 S- 1, 6, T52N, R38W, R39W, 1994, P.S. 17610. The following trees and objects were used to tie the corner position.

Hard Maple	5"	S75°W	27.88'	Soft Maple	N08°E	9.11'
Hard Maple	11"	S09°W	8.80'	Steel Sign Post	East	1.40'

Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date October 07, 1994