

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|-------|-------|
| 1. Public Land Survey | T | <u>52N</u> | R | <u>40W</u> | G-13 | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on October 1, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-13) Standard Corner Sections 33 & 34, T52N, R40W

1846 - William A. Burt set Cedar post

10" Hemlock N 73° E 10 links

12" Hemlock N 57° W 36 links

Closing Corner East 43.56' (Sections 3 & 4, T51N, R40W)

1928 - E.J. Donnelly, C.E., for Supervisor Carroll's Plat of Government Lots 3 & 4, Section 34, shows this corner as a concrete monument and common with Sections to the South.

1969 - M.S.H.D. show the Corner as a star drill in Concrete and common as per Donnelly.

1979 - Robert Mick, P.S. 16936, in Ontonagon County Airport Survey on file with plats at Ontonagon County Register of Deeds, shows that the concrete monument is actually the Closing Corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original Corner and accessories have been obliterated by logging and the passage of time. I found the star drill in concrete as per Donnelly and the M.S.H.D. After extensive retracement in sections to the South and along the township line, I came to the same conclusion as Bob Mick, that E.J. Donnelly and M.S.H.D. mistakenly used the Closing Corner Sections 3 & 4, T51N, R40W as a common corner with Sections North and South of the township line. I re-established the Standard Corner 43.56' West of the Closing Corner as original notes indicate.

Research on file with County Remonumentation Representative.

PLER GROUP APPROVED
Earl W. Appleby
 COUNTY REPRESENTATIVE 10-16-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to read: S. 33, S. 34; T.52N, R.40W; 1996; S.C.; P.S. 37273; COUNTY REMONUMENTATION.

Witnesses:

- | | | | |
|-----------------|---------|--------|------------------------------|
| Closing Corner | East | 43.56' | (Sections 3 & 4, T51N, R40W) |
| 5" Soft Maple | S 06° W | 17.56' | |
| 5" Soft Maple | N 78° W | 20.79' | |
| 5" Soft Maple | N 37° W | 18.92' | |
| Steel Sign Post | North | 0.85' | |

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J. C. Domitrovich

Date 10/15/96

Surveyor's Michigan License No. 37273

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

