

DEC 16 1996

COMMISSION

JUDITH D. ROEHM
 Ontonagon County
 LC 4/128 JEM Fee: 9.00
 Page 1 of 1

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	<u>52N</u>	R	<u>40W</u>	<u>I-12</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Joseph C. Domitrovich, in a field survey on June 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I-12) 1/4 Corner common to Sections 34 & 35, T52N, R40W

1845 - William A. Burt set post

- 12" Hemlock N 54° E 24 links
- 18" White Pine N 37° W 25 links

1922 - E.J. Donnelly C.E. replace corner with an iron bolt from the original White Pine bearing tree. This corner subsequently noted in Supervisor Carroll's Plat of Gov't lots 3 & 4 of this section, in 1928.

1965 - Michigan State Highway Department found a 1/2" iron pipe and gave 3 witnesses and also angle and distance off of centerline control. Numerous private surveys note the same corner as found by the Highway Department.

1988 - Robert Mick P.S. 16936 in survey recorded in Liber 1 page 97 of Surveys shows corner and distance east to center 1/4 corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 5/8" O.D. iron pipe which matched angle and distance well off of centerline control highway M-64. Pipe also worked well with one remaining witness object, and works well with other corners in area as well as with Mick survey.

This pipe has been the long accepted 1/4 corner and I have monumented it as such.

PEER GROUP APPROVED
Carl W. Applekamp
 COUNTY REPRESENTATIVE
 07-08-96

Research on file with County Remonumentation Representative.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 5/8" x 24" rebar with a 3" diameter brass cap stamped to read: 1/4 S.34, S.35; T.52N., R.40W.; 1996; P.S. 37273. Corner falls 5.7' north of centerline Johnson Road and 2.5' west of centerline Noble Road. Also established a reference monument which is a 2" x 30" aluminum pipe with 3" diameter aluminum cap stamped to indicate the 1/4 corner is 24.42' east.

Witnesses:

- 14" White Birch N 68° W 31.60'
- 14" Red Pine N 33° E 60.65'
- Power Pole #10 S 45° E 40.13' (existing nail and tag)
- Anchor Pole S 37° W 37.60'
- Reference Monument West 24.42'

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J.C. Domitrovich

Date 7/3/96

Surveyor's Michigan License No. 37273

