

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Ontonagon (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>52N</u>	R	<u>40W</u>	<u>K-13</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

**SURVEY & REMONUMENTATION**  
**MAY 22 1997**  
**COMMISSION**  
 Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Joseph C. Domitrovich, in a field survey on August 6, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(K-13) Standard Corner Sections 35 & 36, T52N, R40W.

1845 - William A. Burt set a Tamarack Post  
 3" Tamarack N 70° E 17 links  
 4" Tamarack N 49° W 75 links

1923 - E.J. Donnelly re-established corner by proportionate measurement and set an iron pipe. (Map on File at Ontonagon County Abstract and Title.) on his map he noted distances to corners to North, South, East and West. He also noted it fell 5' north and 37' east of an old fence corner.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

All remains of original corner and accessories have been destroyed by draining of the swamp and extensive farming.

I found a 2" pipe 12" below grade in old Township roadbed (running to east). The pipe fell about 50' east of where Laurie Lennivelle (resident of this land for 80 years) remembered a post before it was blasted out for a drainage ditch. Distances to the corners noted in the Donnelly map check reasonably well with this pipe.

I therefore accepted this pipe as the Standard corner and have monumented it as such.

Research on file with County Remonumentation Representative.

**PEER GROUP APPROVED**  
*Earl W. Appelkamp*  
**COUNTY REPRESENTATIVE 08-08-96**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is a 5/8" x 24" rebar driven into a 2" iron pipe and capped with a 3" aluminum cap stamped to read: T.52N., R.40W.; S.35, S.36, S.C.; 1996; P.S. 37273. Corner falls in middle of old Township roadbed running to the east, in the middle of a field and 30' east of a field road to south.

**Witnesses:**

Steel Sign Post	North	8.66'		
Closing Corner Sections 2 & 1, T51N, R40W (2" aluminum pipe w/3" stamped cap)			East	39.60'
Steel Sign Post	S 78° E	40.40'		
"V" Sawed in west end of large culvert on west side of field road south	S 73° W	46.26'		

**NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.**

Signed by Joseph C. Domitrovich Date 8/8/96  
 Surveyor's Michigan License No. 37273

