

**SURVEY &
REMONUMENTATION**

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

JUDITH D. ROEHN
Ontonagon County
LC 4-134 JEM Fee: 9.00
Page 1 of 1

For corners in Ontonagon Located In: _____ Corner Code # _____
(County)

- | | | | | | |
|--------------------------------------|---|------------|---|------------|-------------|
| 1. Public Land Survey | T | <u>52N</u> | R | <u>40W</u> | <u>L-11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	J	K	L	M
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Joseph C. Domitovich, in a field survey on June 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-11) 1/4 Corner common to Sections 25 & 36, T52N, R40W

1845 - William A. Burt set post of Tamarack

4" Spruce N 40° W 47 links

4" Tamarack S 85° E 67 links

1923 - E.J. Donnelly C.E. re-established this corner by single proportionate measurement and set a 3" iron pipe. He used this corner in two plats dated the same year. He indicated corner worked well with old fence intersection.

1991 - Brian Taavola P.S. 21583 found a 3/4" drillrod in a 9" concrete monument in a swamp as per old Highway plans, and recorded it in Liber 3 page 150 of corner records.

1991 - U.S. Army Corps of Engineers found and used the recorded corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found no remains of original corner or accessories. Found the 3/4" drillrod and witnesses as recorded by Taavola. Drillrod falls 2635.21; east of Section corner to west. (Donnelly measured 2635.38' in 1923).

I accepted the drillrod as the 1/4 corner: It falls in a narrow swampy area. I left the drillrod in place and established two reference monuments, one on the north and one on the south side of the swamp.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Carl W. Applekamp
COUNTY REPRESENTATIVE
07-08-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 3/4" drillrod in concrete. Established two reference monuments (R.M.) each a 2" x 30" aluminum pipe with a 3" diameter aluminum cap stamped to indicate bearing and distance to corner. **Note** - Corner does not fall on straight line between reference monuments.

Witnesses:

Lightning rod atop wide smokestack at paper mill bears N 13° 20' 10" 1515' +/-

- | | | |
|-----------------|------------------|-------------------|
| R.M. # 1 | N 01° 37' 08" W | 50.85' |
| R.M. #2 | S 03° 22' 43" E. | 25.94' |
| 6" Poplar | S 89° E | 85.70' (Existing) |
| Power Pole | N 77° E | 75.47' (Existing) |
| Power Pole | N 85° W | 201.94' |
| Steel Sign Post | West | 0.71' |

NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J.C. Domitovich

Date 7/3/96

Surveyor's Michigan License No. 37273

