

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Ontonagon Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey	T	52N	R 40W	L-13
	T	_____	R _____	_____
	T	_____	R _____	_____
	T	_____	R _____	_____
2. Property Controlling in Section	S	_____	T _____	R _____
	S	_____	T _____	R _____
3. Miscellaneous Property in Section	S	_____	T _____	R _____
	S	_____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION
 MAY 22 1997
COMMISSION
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4			3		2		1
3													
4	7			8		9			10		11		12
5													
6	18			17		16			15		14		13
7													
8	19			20		21			22		23		24
9													
10	30			29		28			27		26		25
11													
12	31			32		33			34		35		36
13													

I, Joseph C. Domitrovich, in a field survey on August 7, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
(L-13) South 1/4 Corner Section 36, T52N, R49W.

- 1845 - William A. Burt set Black Ash post
 7" Black Ash N 59° E 35 links
 6" Sugar N 16° W 7 links
- 1923 - E.J. Donnelly C.E., re-established corner position by testimony of Richard Henry who had seen original B.T. and showed Donnelly where it stood. He placed an iron pipe at corner and notes distances to Section corners to East and West. (From map on file at Ontonagon County Abstract & Title.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Original corner and accessories have been destroyed by logging and road construction.

Laurie Lenneville, a resident living in this Section for 80 years showed me a 2" pipe in the middle of an old Township roadbed that had been the long accepted corner. This pipe works well with Donnelly distances to east and west.

I therefore accepted the pipe as the South 1/4 corner of Section 36 and monumented it as such.

Research on file with County Remonumentation Representative.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner is a 3/4" x 48" aluminum rod placed inside a 2" diameter iron pipe and capped with a 3" diameter aluminum cap stamped to read: T.52N., R.40W.; 1/4 S.36, S.C.; 1996; P.S. 37273. Corner falls 65' west of the west bank of the Ontonagon River.

- Witnesses:**
- 6" Soft Maple N 32° W 23.18'
 - Steel Sign Post North 0.80'
 - Iron bolt w/square nut N 12° E 11.16'
 - 3/4" alum. rod w/3" cap East 19.48' (North 1/4 Corner Section 1, T51N, R40W)
 - 10" Soft Maple S 31° W 19.64'



NOTE: Bearings are magnetic. Distances are to nail in side of witness objects unless noted.

Signed by J.C. Domitrovich Date 8/8/96
 Surveyor's Michigan License No. 37273