

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

(ONTONAGON COUNTY)

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53</u> N. <u>X</u> , R. <u>37</u> <u>X</u> W.	C6, MC Bet. C5 & B5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 19, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C6: Original monument and accessories not found. Found old cedar post and old blazed lines which seems to fit good with other corners in area.

Corner MC Between C5 & B5: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C6: Re-established at old cedar post.

Corner MC Between C5 & B5: Re-established on line from D5 across C5 at bank of Lake Superior.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C6: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 6" Cedar S22W 7.8 ft., 1/4S, NBT
 4" Cedar N55W 12.3 ft., 1/4S, NBT
 5" Cedar N86E 9.8 ft., 1/4S, NBT

Corner MC Between C5 & B5: Set 1" I.D. x 30" iron pipe with 4" aluminum cap.
 4" Balsam N69W 5.2 ft., MC, NBT
 12" Maple S30E 15.0 ft., MC, NBT
 6" White Birch S45W 11.3 ft., MC, NBT

Squared 4" White Birch East 2.0 ft.


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 3-18-80
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006