

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	(ONTONAGON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>53</u> N. <input checked="" type="checkbox"/> R. <u>37</u> W. <input checked="" type="checkbox"/>	B7, A7
2. PROPERTY CONTROLLING IN SECTION	<u>18</u> , T. <u>53</u> N. <input checked="" type="checkbox"/> R. <u>37</u> W. <input checked="" type="checkbox"/>	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner B7: Original monument and accessories not found.**
- Corner A7: Original monument and accessories not found. Found two old pipes and scribed post.**
- Corner 15: Not set on original survey nor subsequently, apparently.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner B7: Re-established by proportion between corners east and west.**
- Corner A7: Re-established at old post and pipes.**
- Corner 15: Established by proportion between corners east and west.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner B7: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.**
 6" Maple N52E 12.5 ft., 1/4S, NBT
 11" Cedar S45E 13.1 ft., 1/4S, NBT
 14" Cedar N19W 38.7 ft., 1/4S, NBT
- Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.**
 7" Sugar N38E 13.2 ft., 1/16S, BT
 6" Maple S64E 21.0 ft., 1/16S, BT
 4" Maple S39W 5.2 ft., 1/16S, BT
- Corner A7: Two old pipes and scribed post.**
 12" Cedar N25E 32.6 ft., S18, NBT
 4" Cedar S89E 28.7 ft., S19, NBT 14" Hemlock N26W 45.2 ft., S13, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 7-10-80
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

