

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF --	(ONTONAGON COUNTY) LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53</u> N. <u>X</u> R. <u>37</u> W.	C5 MC Between D5 & E5 MC Between C5 & C4
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____	_____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 18, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner MC Between D5 and E5: Original monument and accessories not found.

Corner C5: Original monument and accessories not found.

Corner MC Between C5 and C4: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner MC Between D5 and E5: Re-established on line from C5 across D5 to bank on shore of Lake Superior.

Corner C5: Re-established by double proportion.

Corner MC Between C5 and C4: Re-established on line from C6 across C5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner MC Between D5 & E5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 6" Cedar S74W 50.1 ft., MC, NBT
 7" Sugar S08W 14.2 ft., MC, NBT

Corner C5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 8" Sugar S67E 26.8 ft., S17, NBT
 5" Sugar N28W 32.2 ft., S 7, NBT
 7" W. Birch S41W 10.2 ft., S18, NBT

Corner MC Between C5 & C4: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 9" Spruce S05W 5.9 ft., MC, NBT
 6" Spruce S78E 24.9 ft., MC, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____
CHIEF OF SURVEY PARTS
MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

