

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

ONTONAGON Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53N</u> N. S., R. <u>37W</u> E. W.	<u>E6, MC Between E6 & E5</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 25, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E6: Original monument and accessories not found.
Corner MC Between E6 & E5: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E6: Restored on a line projected from E8 across E7 at record distance from E7.
Corner MC Between E6 & E5: Restored on line projected across E6 from E7.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E6: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 6" Maple S65°E 16.8 Ft. 1/4 S, NBT
 5" Y. Birch N06°E 16.7 Ft. 1/4 S, NBT
 9" Maple S82°W 48.3 Ft. 1/4 S, NBT

Corner MC Between E6 & E5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 4" Cedar N30°E 5.4 Ft. MC, BT
 9" Cedar S32°E 16.0 Ft. MC, BT
 7" Cedar S34°W 18.2 Ft. MC, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE _____

CHIEF OF SURVEY PARTY
Keith L. Sackett
 MICHIGAN REGISTERED LAND SURVEYOR

Keith L. Sackett
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

