

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

ONTONAGON CO

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>53N</u> N. S., R. <u>37W</u> E. W.	<u>E7</u>
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	, T. <u>53N</u> N. S., R. <u>37W</u> E. W.	<u>15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 26, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner E7: Original monument and accessories not found. Found old signature tree 14" Cedar N72°E 23 Ft. and other old blazes and markings.
Corner 15: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
Corner E7: Restored by proportion between corners east-west-south and stream north.
Corner 15: Established on line and midway between corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner E7: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 24" Cedar S05°W 6.3 Ft. S21, NBT
 18" Cedar N40°E 30.6 Ft. S16, NBT
 4" Sugar N17°W 16.9 Ft. S17, NBT
Corner 15: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
 10" Y. Birch S10°E 6.1 Ft. 1/16S, BT
 4" Y. Birch West 10.0 Ft. 1/16S, BT
 5" Y. Birch N45°E 3.2 Ft. 1/16S, BT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80
 CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

