

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

ONTONAGON Co

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>53N</u> N. S., R. <u>37W</u> E. W.	MC Between G6 & G5 F9
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 16, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner MC Between G6 & G5: Original monument and accessories not found.
Corner F9: Original monument and accessories not found.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner MC Between G6 & G5: Restored on shore of Lake Superior by projecting a line from G7 through G6.
Corner F9: Restored on line and midway between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner MC Between G6 & G5: Set 1" I.D. x 36" iron pipe with 4" aluminum cap.
DNR Ref. Tag and Nail in:
6" Cedar S62°W 6.16 Ft. MC, NBT
4" Ash N80°E 23.51 Ft. MC, NBT

Corner F9: Set 1" I.D. x 36" iron pipe with 4" aluminum cap. DNR Ref. Tag and Nail in:
14" Sugar N84°E 3.56 Ft. 1/4 S, NBT
14" Sugar N41°W 7.24 Ft. 1/4 S, NBT
5" Spruce S59°W 15.61 Ft. 1/4 S, NBT

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 2/6/80

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR
Keith L. Sackett
Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006

