

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

## ONTONAGON COUNTY

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 53 N. R. 37 W.	A6
2. PROPERTY CONTROLLING IN SECTION	18, T. 53 N. R. 37 W.	10
3. MISCELLANEOUS PROPERTY IN SECTION	, T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **Keith L. Sackett**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on **March 17,** 19**81**, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**Corner A6: Original monument and accessories not found. Corner falls in area of many old cedars.**

**Corner 10: Not set on original survey nor subsequently apparently.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**Corner A6: Restored at a mean bearing to other north south lines at record distance from corner south.**

**Corner 10: Established midway and on line between corners north and south.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**Corner A6: Set 1" I.D. by 32" iron pipe with 4" alum. cap.**  
10" Cedar S19E 18.6 ft. 1/4S,NBT  
18" W. Pine N04W 14.4 ft. 1/4S,NBT  
12" Maple S75W 22.5 ft. 1/4S,NBT

**Corner 10: Set 1" I.D. by 32" iron pipe with 4" alum. cap.**  
12" Cedar S15E 5.3 ft. 1/16S,BT  
8" Cedar S80W 17.0 ft. 1/16S,BT  
8" B. Ash N18E 12.3 ft. 1/16S,BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY *Keith L. Sackett* DATE **1-26-82**

CHIEF OF SURVEY PARTY  
**Keith L. Sackett**  
MICHIGAN REGISTERED LAND SURVEYOR  
Michigan Dept. of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006