

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Ontonagon

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>53N</u> R <u>37W</u>	<u>C6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 13 2003

Stephan J. Szyszkoski

I, _____, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. Reestablished in 1980 by K.L. Sackett RLS at location of old cedar post and old blazed lines. Set 1"IDx36" I.pipe with 4" aluminum cap. 6" Cedar S22W 7.8', 4" Cedar N55W 12.3', 5" Cedar N86E 9.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) Recovered the monument in good condition and at record bearing and distance from the 1982 witnesses, all of which have been windthrown. Rough measured north and south to adjacent section corners and found the distances to be 2597' and 2609', respectively. Accepted the monument as marking the corner position and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Found 1" ID I.pipe with 4" alum.

MDNR cap. Blazed, scribed, and set

measuring nails in:

6" Cedar N47E 15.5' "1/4S NBT"

8" Cedar S67E 34.6' do

5" Aspen S18E 11.9' do

6" Aspen N81W 15.3' do

Bearings are magnetic. Distances are to

nail with tag. Sq'd 1.5" dia. Cedars

1.5' W'ly and 1.5' S'ly



Signed by Stephan J. Szyszkoski

Date 12/17/03

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities