

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 53 N.R. 38 W


Ontonagon COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 22-23

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/26/65

WITNESSES TO CORNER..... 12" Y. Birch (1/4S 22/23 NBT), East 05 1/2 Links



18" Soft Maple, (1/4S NBT), N 35° W, 12 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established on line with Section Corner to North and an Original Y. Birch Line tree 7.77 chains to South.
Found some blazes 1 chain North but no Original evidence here or at corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 7, 1965
REGISTERED LAND SURVEYOR