

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 53 N.R. 38 W


Ontonagon COUNTY

DESCRIPTION OF CORNER Meander Corner between Secs. 14-15 on Lake Superior

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 2/16/1965

WITNESSES TO CORNER..... 24" W. Pine, (M.C. 14/15 NBT), S50°W, 35 Links



16" W. Pine, (M.C. 14/15 NBT), S 56° E, 56½ Links

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was re-established at lake by extending bearing of Section line between Secs. 22-23. Found no evidence of Original line. Corner lies 20.57 chs. North of Section Corner 14-15-22-23.

**SURVEYOR'S SEAL**

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE April 7, 1965  
REGISTERED LAND SURVEYOR