

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 38W	G9
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 22 T 53N R 38W	3
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 3 06/23/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1965 - Remonumented by Billy D. Buckler RLS. Set 1" I.pipe with 4" aluminum cap buried in road. Placed location poster 10 links west of corner. Squared tree 21 links West. Witnesses to the corner were not transcribed to the official land corner record but appear in the field notes: 11" Cedar S69W 41.5 links, 10" Hemlock N79E 41 links.

(3-Sec. 22) North 1/16 corner between Sections 21 and 22. 1965 - Established by Billy D. Buckler midway and on line between Section and Quarter corners north and south. Set 1" pipe with 4" alum. cap. 8" Soft Maple S27E 30.5', 15" Hemlock N25W 44.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) Found the 1965 monument, in good condition but with a small portion of the cap broken off, buried about 5" below the surface of and in the approx. C/L of a N-S winter road, at record bearing and distance from the remaining 1965 NBT Cedar SW, in good condition with overgrown blazes. Accepted the monument as the best available evidence of the position of the original corner. Found a 3/4" iron pipe, not of record, West 6.36' projecting approx. 16" above ground at the west edge of the road. Drove the 3/4" pipe down to 5" below ground surface. The 1965 NBT Hemlock was not recovered.

(3-Sec. 22) Restablished the corner midway and on the Section line between Section corner 1329.49' north and Quarter corner 1329.49' south. The position for the corner falls in a N-S winter road and is likely to be disturbed. Left corner position proper unmonumented and set a Reference Corner N89 deg. 39'29"E 33.00' from the corner position (MCS83 grid bearing).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 15" Cedar S73W 27.8' old blazes
 4" Maple N67E 17.85' mrkd "S22 NBT"
 5" Y.Birch S50E 18.35' "S27 NBT"
 6" Maple S36W 22.95' "S28 NBT"
 Fd Sq'd cedar post West 6.6'
 Bearings are magnetic.

(3) Set 1"IDx32" I.pipe with 4" alum. MDNR cap 33.00' easterly from the corner position for a REFERENCE MONUMENT. Set measuring nail with MDNR tag in the side of:
 15" Hemlock N12W 11.3'
 5" Spruce N49E 5.95'
 6" Maple S28E 7.65'
 8" Maple S82W 5.0'
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division