

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 38W	G7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 22 T 53N R 38W	10
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

G7 06/10/2010

I, Stephan J. Szyszkoski, in a field survey on 10 06/10/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(G7) Corner common to Sections 15-16-21-22. 1965 - Reestablished by Billy D. Buckler RLS. Old roads North, South, and East from corner. Set 1" pipe with 4" alum. cap. 12" Hemlock N05W 42.6', 14" Soft Maple N54E 54.6'.

(10-Sec. 22) South 1/16 corner between Sections 21 and 22. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G7) Found the 1965 monument in good condition and at record bearing from the Hemlock NBT NW, in good condition with overgrown blazes. The Maple NBT NE was not recovered. The Hemlock NBT was found approx. 44.6' (to overgrown notch), 2 feet further than Mr. Buckler's record, which record appears to be in error. Checked the position of the monument with respect to 1965 1/16 and 1/4 corner monuments to the east and found position to be in order. Accepted the monument as the best available evidence of the position of the original corner.

(10-Sec. 22) Established the corner midway and on the Section line between Section corner 1239.03' south and Quarter corner 1239.03' north. The east edge of a N-S winter road is 8' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G7) Fd. 1"ID I.pipe with 4" brass MI Dept of Conservation cap. Set measuring nail with MDNR tag in the side of:
 14" Hemlock N02W 45.05' 1965 NBT
 8" Maple S47E 25.7' mrkd "1/4S NBT"
 5" Maple S55W 7.05' do
 13" Hemlock N50W 17.2' do
 3/4" ID iron pipe, 3.1' tall, adjacent.

(10) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Maple N11E 31.2' mrkd "1/16S BT"
 6" Maple S62E 13.25' do
 3" Balsam S22E 21.8' do
 3" Maple S54W 37.85' do
 Sq'd cedar post adjacent. Bearings magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16481
16482