

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 53N R 38W	G8
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 15 T 53N R 38W	16
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	11	12	13	14	15	16	17	18	19	20	21	22
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 16 03/08/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G8) Quarter corner common to Sections 21-22. 1965 - Remonumented by Billy D. Buckler RLS from one Soft Maple B.T., found green with face rotted. Corner lies in old N-S road. Set 1"ID I.pipe with 4" aluminum cap. 13" Cedar S84E 28.0', 11" Y.Birch S24W 22.4'.

(16-Sec. 15) East 1/16 corner between Sections 15 and 22. 1965 - Established by Billy D. Buckler RLS midway and on line between Section corner to East and 1/4 corner to West. Set 1"ID I.pipe with 4" aluminum cap. 9" Cedar N74W 11 links, 12" Cedar S65W 57 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G8) Found the 1965 monument in good condition and at record bearing and distance from the remaining NBT Cedar SE, in good condition with scribing visible. The Y.Birch NBT was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(16-Sec. 15) Found the 1965 monument in good condition and at record bearing and distance from the remaining 1965 cedar BT NW, in good condition with scribing visible. An old cedar post is standing, adjacent. Checked the position of the monument with respect to Section and 1/4 corners east and west and found it to be substantially in accord with the record. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G8) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 14" Cedar S79E 28.25' 1965 NBT
 4" Maple S09E 34.45' mrkd "1/4S NBT"
 6" Maple S55W 51.95' do
 4" Y.Birch N11E 28.3' do
 Sq'd cedar post adjacent. Bearings magnetic.

(16) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar N69W 7.4' 1965 BT
 5" Maple N41E 17.75' mrkd "1/16S BT"
 3" Sugar S38E 16.95' do
 5" Sugar S44W 8.9' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16480

16479