

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 15 T 53N R 38W	SMC N. of #16
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 06/28/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(SMC N. of #16) Special Meander Corner north of 1/16 corner #16, Section 15, on the shore of Lake Superior at its intersection of the East 1/16 line, Section 15. Not established in the original survey. 1965 - Billy D. Buckler RLS placed a monument the position of which was made erroneous by the remonumentation of Quarter corner G6 in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(SMC) Established the corner at the intersection of the East 1/16 line of Section 15 with the shoreline of Lake Superior. The monument was placed in mineral soil at the top of an approx. 4' high ridge above the Lake Superior shore. The bearing of the East 1/16 line is the mean of the bearings of the East Section line and the N-S 1/4 line. The corner is located 1747.13' north of 1/16 corner #16, Sec. 15. The 1965 monument was not recovered and is presumed to have been destroyed by erosion. A 4-wheeler trail runs along the ridge and is immediately south of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(SMC) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 10" W.Birch N50W 15.0' mrkd "SMC BT"
 7" W.Birch N05W 6.65' do
 11" W.Birch S18E 19.3' do
 4" W.Pine S59W 13.05' do
 Sq'd cedar post adjacent. Bearings magnetic.



Signed by Stephan J. Szyszkoski Date 08/25/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division