

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Ontonagon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 15 T 53N R 38W	8
	S 15 T 53N R 38W	PCC 1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on PCC 1 06/21/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 15) West 1/16 corner, Section 15. Not established in the original survey. Monumented in 1965 by Billy D. Buckler RLS in a position made erroneous by the 1982 monumentation of the 1/4 corner between Sections 15 and 16.

(PCC 1-Sec. 15) Property controlling corner being the northeast corner of a parcel of land described in L.92 of Deeds, P.41, Ontonagon County Records. This corner is 1600.00 feet north of the Quarter corner between Sections 15 and 22 and is on the N-S 1/4 line of Section 15.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 15) The 1965 monument was recovered and was destroyed. Established the corner midway and on a straight line between the 1982 Quarter corner 1349.72' west and Center of Section 15 1349.72' east.

(PCC 1-Sec. 15) Established the corner on the N-S 1/4 line of Section 15, 1600.00' north of the Quarter corner common to Sections 15 and 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 8" Maple N32W 18.35' mrkd "1/16S BT" 11" Cedar S81E 19.3' do 10" Cedar S16E 16.0' do 7" Maple S69W 9.5' do Sq'd cedar post adjacent. Bearings magnetic.	PCC 1- Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 13" Cedar N42E 15.8' mrkd "PCC BT" 8" Maple S10W 10.3' do 7" Maple S61W 16.15' do 11" Maple N33W 17.45' do Sq'd cedar post adjacent. Bearings magnetic.
--	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/25/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

16483
16484