

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. PA 1970

|   |                         |               |
|---|-------------------------|---------------|
| For Corners in:<br>Presque Isle<br>(County) | Located In              | Corner Code # |
| 1. Public Land Survey                       | T _____ R _____         | _____         |
|   | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section       | S 29 T 33N R 2E         | 16            |
|   | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Section     | S _____ T _____ R _____ | _____         |
|   | S _____ T _____ R _____ | _____         |
| 4. Lot No: _____                            | Recorded Plat: _____    |               |
| 5. Private Claims: _____                    |                         |               |

Register of Deeds Stamp & File Number

|    |    |   |    |   |    |   |    |   |    |   |    |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

I, Carl T. Kiiskila, in a field survey on August 6, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

16- Michigan Department of Conservation surveyor Marcus Schaaf R.L.S. #3104 sunk iron for corner while surveying in the area circa 1940. No witnesses or type of monument given.

Kenneth J. Ostling R.L.S. #10068 found and accepted this corner while doing a survey in the NE 1/4 of section 32 T.33N.,R.2E in September 1979.

Perla Stout Associates, P.C. Found 1 1/2" pipe for the corner while surveying in the area in 1978.

Wit: N42°E 3" Maple 18.85'  
S25°E 4" J. Pine 32.75'  
S80°W 6" Oak 10.68'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

16- Found 1 1/4" pipe as set by Marcus Shaaf and Accepted by Kenneth J. Ostling.

Note: This corner is 3' East of its technical location, however, it has been accepted as it was found in view of its long standing acceptance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

16- Found 1 1/4" pipe

Wit: 10" Oak S78°W 10.65'  
13" Oak N28°E 43.44'  
4" Maple S61°E 56.64'  
7" Maple S50°E 45.92'  
Blue Carsonite Post North 1'±



Signed by: Carl T. Kiiskila  
Surveyor's Michigan License No.: 33981

Date: 8-26-02