

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 33. NR. 4 E.

Presque Isle COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 10 and 15

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

- \* W. Pine 6" - S12E - 23.7 feet
- \* Cedar 7" - N56W - 61.9 feet

\* G. F. DeLaMater NBTs

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division Land Surveyor while making a survey of Section 15. Found  $\frac{1}{2}$ " iron bar in place as restored by G. F. DeLaMater in 1944. Stumps of both government Tamarack BTs in place, the NW showing evidence of notch of lower face. Very old post bottom in place here also. A 1" pipe by unknown is S62E about 65 links. This point does not conform too well for midpoint or line on this mile, but the evidence appears to outweigh the erroneous measurements.

Corner was placed and witnesses noted May 5, 1960.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*  
REGISTERED LAND SURVEYOR

DATE 5/6/60