

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 33 NR. 4 E

Presque Isle COUNTY

DESCRIPTION OF CORNER Witness Corner between Sections 15 and 16,
located 5.44 ch north of corner to Sections 15-16-21-22
DESCRIPTION OF CORNER MONUMENT Placed 1" pipe with brass cap over
 $\frac{1}{2}$ " iron bar

WITNESSES TO CORNER

16" R. Pine - Due East - 61 $\frac{1}{2}$ links
* 9" J. Pine - N51W - 24 links
* 8" J. Pine - N68E - 80 $\frac{1}{2}$ links

* G. F. DeLaMater MBTs of 1945.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was found by Forestry Division Land Surveyor while making a survey of Section 15. Found a $\frac{1}{2}$ " iron bar at corner as restored by G. F. DeLaMater in 1945. Both government BT stumps in place the NW showing a good face, but the bearing to this BT is somewhat north of West. Corner was set to control location of Section corner in pond which is corner of state ownership.

Corner was placed and witnesses noted May 5, 1960.

SURVEYORS SEAL

SIGNED Kenneth J. Velling DATE 5/6/60
REGISTERED LAND SURVEYOR