

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Presque Isle  
 (County)

Located In: \_\_\_\_\_ Corner Code ##

- |                                       |                          |             |
|---------------------------------------|--------------------------|-------------|
| 1. Public Land Survey                 | T <u>33N</u> R <u>4E</u> | <u>J-11</u> |
|                                       | T <u>33N</u> R <u>4E</u> | <u>I-11</u> |
|                                       | T <u>33N</u> R <u>4E</u> | <u>H-11</u> |
|                                       | T <u>33N</u> R <u>4E</u> | <u>I-13</u> |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____       |
|                                       | S _____ T _____ R _____  | _____       |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Carl R. Johnson, in a field survey on May 20, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-11 - Found evidence of old post point and witnesses (NBT) by Scott Engineering Survey.
- I-11 - Set by double proportion from found corners.
- H-11 - Found original post point and post and witnesses (NBT) by Scott Engineering Survey.
- I-13 - Found 3/4" pipe in place in line with County Road South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


J-11 - S 1/2 Corner  
 DNR Mon & cedar post  
 Maple 4" N34°W 20.5' (1/2, NBT)  
 Maple 6" N46°E 25.3' (1/2, NBT)  
 Red Oak 10" S8°E 23.2' (1/2, NBT)

I-11 - SW Corner  
 DNR Mon. & cedar post  
 Squared cedar 4" North .6'  
 Cedar 8" N8°E 6.3'  
 Cedar 8" N75°W 11.5'  
 Cedar 8" S32°W 41.0'  
 Cedar 7" S5°E 22.2'

H-11 - S 1/2 Corner  
 DNR Mon - cedar post  
 Cedar 5" N35°W 13.5' (1/2, NBT)  
 Cedar 7" N57°E 11.7'  
 Cedar 6" S34°E 5.6'  
 Cedar 5" S51°W 11.6'

I-13 - SW Corner  
 DNR Mon - cedar post  
 Cedar 12" N1°W 12.4' (S34, NBT)  
 Cedar 10" N38°E 23.0' (S35, NBT)  
 Balsam 14" S16°E 19.3' (S2, NBT)

Signed by Carl R. Johnson  
 Surveyor's Michigan License No. 30083



Date 1/4/88