

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Presque Isle (County)	Located In	Corner Code #	
1. Public Land Survey	T 33N R 8E	J-11	
2. Property Controlling in Section	S 35 T 33N R 8E	5	
3. Miscellaneous Property in Section	S T R		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on January 19, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11 G.L.O. Josiah Knauer D.S. July 1855
Set quarter section post
Wit: Poplar 6 S61°W 16 links
Poplar 7 N15°E 3 links

5- Liber 231, Page 313 July 1979 Duane R. MacNeil Shows corner. Type of monument or witnesses not given.

Liber 231, Page 313 July 1979 Duane R. MacNeil set a 1" pipe for corner.

Wit: 10" Beech N75°E 9.57'
10" Aspen S10°E 15.87'
10" Aspen N50°W 20.23'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

J-11 Found a 3/4" capped iron pipe, with D.R. MacNeill L.S. cap #19237 as set by D.R. MacNeil.

5- Found 3/4" iron pipe with D.R. MacNeill L.S. cap #19237 for the N 1/16 corner on the North and South 1/4 line of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-11 3/4" Pipe with L.S. cap #19237 D.R.M.
Wit: 4" Balsam N27°E 28.67'
4" Balsam S87°E 27.18'
2" Cedar N52°W 17.01'
2" Balsam S04°W 24.69'

5- 3/4" Pipe and stones with L.S. Cap #19237 D.R.M.
Wit: 2" Maple South 12.34'
4" Maple S61°W 10.81'
3" Maple N27°E 11.03'
10" Maple N88°E 18.11'

Signed by: _____

Carl T. Kiiskila

Date: _____

10-21-03

Surveyor's Michigan License No.: 33981

