

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Presque Isle (County)	Located In	Corner Code #	
1. Public Land Survey	T 33 N R 8 E	K-10	
	T _____ R _____		
2. Property Controlling in Section	S 26 T 33 N R 8 E	9	
	S _____ T _____ R _____		
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Carl T. Kiiskila, in a field survey on May 25, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-10 GLO Josiah Knauer, D.S. July 1855
Set quarter section post
Wit: 5" Tamarack N31°E 27 links
5" Tamarack S46°W 16 links

9- This corner was not established during the original government survey.

Earl T. Lewis P.S. #27452 Found an existing cedar stake for corner No date or witnesses given.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-10 Found a square cedar stake fitting Earl T. Lewis's distance North.

9- Established the Northwest corner of the Northeast quarter of the Southeast quarter of section 26 per standard B.L.M. instruction for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10 Set DNR monument
Wit: 3" Cedar East 6.72'
6" Cedar S39°E 5.87'
6" Cedar N37°W 10.35'
5" Cedar N35°E 9.80'
Carsonite post North 1' ±

9- Set 5/8" x 32" rerod w/ PS cap #33981
Wit: 8" Cedar S16°W 14.91'
5" Cedar S81°W 7.64'
3" Cedar N01°E 5.49'
6" Cedar S68°E 2.33'
Carsonite post North 1' ±

Signed by: _____

Carl T. Kiiskila

Date: _____

10-21-03

Surveyor's Michigan License No.: 33981

