

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Presque Isle (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>33N</u> R <u>8E</u>	<u>I-8</u>	
	T <u>33N</u> R <u>8E</u>	<u>J-12</u>	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on February 02, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

I-8 GLO Josiah Knauer, D.S. 1856  
 Set quarter section post  
 Wit: 9" Beech N71°E 38 links  
 10" Beech S78°W 14 links

J-12 Liber 231 Page 311 Duane R. MacNeil shows a 3/4" pipe for the corner.

Wit: 10" Beech S85°E 1.75'  
 14" Beech Due North 12.35'  
 16" Beech N60°W 22.47'

May 1981 Earl T. Lewis #27452 found existing 1/2" rod for the corner.

Wit: T. Pole N45°E 62.82'  
 T. Pole N45°W 55.01'

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

I-8 Found a 1/2" rerod in a monument box fitting E.T. Lewis's survey in section 23.

J-12 Found 3/4" capped iron with P.S. Cap #19237 fitting D.R. MacNeil's survey in section 35.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

I-8 Found 1/2" Rerod in monument box  
 Wit: Telephone pole N40°W 55.29'  
 Telephone pole N51°E 63.17'  
 Telephone pole S42°E 74.21'  
 3" Cedar S44°W 108.25'

J-12 3/4" Pipe with P.S. cap #19327 D.R.M.  
 Wit: 20" Beech N21°W 22.55'  
 18" Beech N40°E 12.36'  
 12" Beech S41°E 1.70'  
 10" Twin Basswood S18°W 18.82'

Signed by: \_\_\_\_\_

Carl T. Kiiskila

Date: \_\_\_\_\_

10-21-03

Surveyor's Michigan License No.: 33981

