

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Presque Isle (County)	Located In	Corner Code #	
1. Public Land Survey	T _____ R _____		
	T _____ R _____		
2. Property Controlling in Section	S <u>26</u> T <u>33 N</u> R <u>8 E</u>	<u>6</u>	
	S <u>26</u> T <u>33 N</u> R <u>8 E</u>	<u>7</u>	
3. Miscellaneous Property in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
4 Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiskila, in a field survey on May 25, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

6- This corner was not established during the original government survey.

7- Earl T. Lewis P.S. #27452 set this corner while doing a survey in section 26, July 1983.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

6- Established the Southwest corner of the Northeast quarter of the Northeast quarter of section 26 per standard B.L.M. instructions for the subdivision of a section.

7- Found a 1/2" rod with P.S. cap #27452 as set by E.T. Lewis.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

6- Set 5/8" x 32" rerod w/ PS cap #33981
 Wit: 10" Cedar N76°E 5.91'
 5" Cedar N22°E 9.09'
 10" Cedar West 11.89'
 12" Cedar S30°E 5.35'
 1/2" rod w/ cap East 7.35'
 Carsonite post North 1' ±

7- 1/2" rerod w/ P.S. cap #27452
 Wit: 3" Ash N05°E 6.84'
 4" Balsam N55°E 6.31'
 4" Balsam S30°E 11.11'
 5" Balsam S54°W 4.89'
 Carsonite post North 1' ±

Signed by: Carl T. Kiskila
 Surveyor's Michigan License No.: 33981

Date: 10-21-03

