

8606

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC -2 PM 2:11

For corners in

Presque Isle
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34 R 4E

A-2 ✓

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Janet M. Lamb
REGISTER OF DEEDS

DEC 29 1999

SECTION
Register of Deeds Stamp & File Number

I, Delmer E. Porter in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-2 GLO Notes - 1855
Set 1/4 Section Post
Y Pine 18" S60°W 3 Lks
Y Pine 8" N30°W 14 Lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2 Found Nothing
Set 1/2" Rod & RLS Cap #15410
By Single Proportion


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 1/2" Rod & Cap by S.P.
S50°W 30.54' 23" Oak
N38°W 74.83' 9" Red Pine
N50°E 30.18' 10" Red Pine
S51°E 26.87' 7" J. Pine

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Quinn*
Date 11/30/99

*Witness tags & nails used.



Signed by *Delmer E. Porter*

Surveyor's Michigan License No. #15410

Date 11-15-99