

8607

1999 DEC -2 PM 2:11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Jenice M. Lamb
REGISTER OF DEEDS

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T34 R 4E	A-3 ✓
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED

DEC 29 1999

SECTION
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Delmer E. Porter in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-3 GLO Notes - 1855
Set Post
Y. Pine 22" N42°W 69½ Lks
Y. Pine 10" S33°W 58 Lks

C. Kiiskila #33981
Fd. P.I. Co. Monument
Twin Oak N51°E 66.76'
6" W. Pine N21°W 25.14'
4" R. Pine S50°W 29.47'
5" R. Pine S38°E 55.36'
L. 322, Page 426

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 Fd. 4" Conc. Mon/Brass Cap
Twin Oak N51°E 66.76'
6" W. Pine N21°W 25.14'
4" R. Pine S50°W 29.47'
5" R. Pine S38°E 55.36'



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 4" Conc Mon/Brass Cap
S51°W 29.45' 5" Red Pine
N22°W 25.10' 8" Red Pine
N50°E 66.68' 8" Twin Oak
S39°E 55.39' 7" Red Pine

Ratified by Peer Group
in accordance with P.A. 345
Chairman Norman J. Olanic
Date 11/30/99

*Witness tags & nails used.

Signed by Delmer E. Porter
Surveyor's Michigan License No. #15410

Date 11-15-99