

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1999 DEC -2 PM 2:11

For corners in

Presque Isle
(County)

Located In:

Corner Code #

1. Public Land Survey

T	34	R	4E	A-5 ✓
T	_____	R	_____	_____
T	_____	R	_____	_____
T	_____	R	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____
S	_____	T	_____	_____

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

Janet M. Lamb
REGISTER OF DEEDS

DEC 29 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Delmer E. Porter in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5 GLO Notes - 1855
Set Post Cor of Sects 12&13
T34N, R3E
Sp Pine 9" N69°W 49 Lks
Sp Pine 9" S60°W 62 Lks

C. Kiiskila #33981, L 1, Page 1010
Fd. P.I. County Mon
N25°W 72.13' 14" R. Pine
N47°E 31.93' 22" W. Pine
S77°W 37.82' 22" R. Pine
S23°E 18.21' 18" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found 4" Conc Mon in Place
N30°W 72.15' 14" N. Pine
N43°E 32.01' 18" W. Pine
S75°W 37.89' 20" R. Pine
S28°E 18.46' 14" Oak



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 Conc Mon/Brass Cap
S75°W 37.89' 20" R. Pine
N30°W 72.15' 14" N. Pine
N43°E 32.01' 18" W. Pine
S28°E 18.46' 14" Oak

Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Quinn*

Date 11/30/99

*Witness Tags & nails used.

Signed by *Delmer E. Porter*
Surveyor's Michigan License No. #15410

Date 11-15-99