

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34</u> R <u>4E</u>	<u>A-9</u> ✓
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

PRESQUE ISLE COUNTY
RECORDED

1999 DEC -2 PM 2: 12

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Delmer E. Porter in a field survey on Nov. 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-9 GLO Notes - 1855
- Set Post & Corrected
- 10" Maple N15°E 27 Lks
- 14" Birch S71°E 12 Lks
- 17" Birch S52°W 9 Lks
- T. Hall #41100
- Fd. 1/2" Rod & Cap #15410
- N73°W 2.51' 7" Birch
- S87°E 18.06' 6" Maple
- S42°W 20.81' 18" Oak
- S53°E 19.08' 12" Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-9 Fd. 1/2" Rod & Cap #15410
- N73°W 2.51' 7" Birch
- S87°E 18.06' 6" Maple
- S42°W 20.81' 18" Oak
- S53°E 19.08' 12" Oak



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-9 1/2" Rod & Cap #15410
- S42°W 20.81' 18" Oak (OW)
- N73°W 2.51' 7" Birch (OW)
- S87°E 18.06' 6" Maple (OW)
- S53°E 19.08' 12" Oak (OW)

*Witness tags & nails used.

Ratified by Peer Group
in accordance with P.A. 345

Chairman Norman J. Orami
Date 11/30/99

Signed by Delmer E. Porter
Surveyor's Michigan License No. #15410

Date 11-15-99