

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Presque Isle (County)	Located In:	Corner Code #
1. Public Land Survey	T34 R 4E	A-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

PRESQUE ISLE COUNTY
RECORDED
1999 DEC -2 PM 2:12
Jane M. Lamb
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Delmer E. Porter in a field survey on Nov. 11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 GLO Notes - 1855 Set 1/4 Sec Post 8" Pine S31°W 9 Lks 18" Pine N34°W 29 Lks	R. Bischer #22428 1" Pipe N65°E 14.96' 14" Oak S17°E 9.36' 12" Oak N34°W 19.14' G.B.T. Stump
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 Found 1" Pipe
Found 2 of Bischer's Witnesses
Found 2 other witnesses not of record
All have nails and no tags



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 1" Pipe
N80°W 41.70' 20" J. Pine
N47°W 48.30' 21" Oak
N67°E 14.96' 17" Oak
S17°E 9.40' 17" Oak

Ratified by Peer Group
in accordance with P.A. 345
Chairman *Norman J. Quinn*
Date 11/30/99

*Witness tags & nails used.

Signed by *Delmer E. Porter*
Surveyor's Michigan License No. #15410

Date 11-15-99