

**1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,
LAND CORNER REMONUMENTATION**

LIBER 335 PAGE 210

DEC 29 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
PRESQUE ISLE

(County)

Located in: **BISMARCK TWP.** Corner Code # **C-1** ✓
T34N R 4E
 T ___ R ___
 T ___ R ___
 T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Recorded Dec 20, 1999
 At 10:30 o'clock A M
Janet M. Lamb
 Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

James A. Beck in a field survey on **Dec 9, 1999** do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-1 1840 G.L.O. by John Hodgson (Twp. Boundary) PA 74 Certificate by Kenneth Ostling dated 9-04-80
 "Set post cor. of Secs 31 and 32"
 S. Pine 10, N47E 28
 S. Pine 10, N 63W 34
 "Set by single proportionate measure between corners
 1/2 mile East and 1 mile West"
 Set DNR Monument
 9" Red Pine S63°W 5.0'
 9" R. Pine N19°E 5.3'
- 1856 G.L.O. by Alfred Millerd
 "Intersect Township Boundary at Post"
 Spruce Pine 12 S5W 96; Spruce Pine 6 S56E;

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-1 November 9, 1999 Remonumentation by James A. Beck P.S. 21559
 Found DNR Monument
 S63°W 5.0' 12" Red Pine
 N19°E 5.3' 12" Red Pine
 Planning Dept Group in accordance with P.A. 345
 Chairman *Norman J. Quinn*
 Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-1 November 9, 1999 Remonumentation by James A. Beck P.S. 21559
 DNR Monument
 S63°W 5.23' 12" Red Pine P.S. 21559 tag
 N19°E 5.94' 12" Red Pine P.S. 21559 tag
 N45°W 37.72' 7" Red Pine P.S. 21559 tag
 S50°E 22.10' 12" Red Pine P.S. 21559 tag

Corner falls in woods at Northwesterly corner of recent clearcut area

Signed by *James A. Beck*
 Surveyor's Michigan License No. 21559

Date 12-18-1999

