

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,

LAND CORNER REMONUMENTATION

LIBER 335 PAGE 211

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
PRESQUE ISLE

Located in: **BISMARCK TWP.** Corner Code #: **c-2** ✓
 1. Public Land Survey **T 34 N 4 E**
 T R
 T R
 T R
 T R
 2. Property Controlling in Section **S T R**
 S T R
 3. Miscellaneous Property in Sec. **S T R**
 S T R

Recorded Dec 20, 1999
 At 10:30 o'clock A M
Janet M. Lamb
 Reg. of Deeds, Presque Isle Co. MI
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

James A. Beck, in a old survey on Nov 9, 1988 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-2
 1840 G.L.O. by John Hodgson (Twp. Boundary) 1856 G.L.O. by Alfred Millerd "Intersect Township Boundary at Post"
 Set post cor. of Secs 31 and 32" Spruce Pine 12 53W 96
 S. Pine 10, N4E 28 Spruce Pine 6 556E 77
 S. Pine 10, N 63W 34 Kenneth Ostling dated 9-04-80, "Set by single proportionate measure between corners 1/2 mile East and 1 mile West" Set DNR Monument
 9" Red Pine 563°W 5.0' ; 9" R. Pine N19°E 5.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-2 found DNR Monument and following witnesses from Ostling recordation

563°W 5.23' 12" Red Pine
 N19°E 5.94' 12" Red Pine

Witness by Peer Group
 in accordance with P.A. 345
 Chairman Norman J. Owen
 Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-2 DNR Monument
 563°W 5.23' 12" Red Pine P.S 21559 tag
 N19°E 5.94' 12" Red Pine P.S 21559 tag
 N45°W 37.72' 7" Red Pine P.S 21559 tag
 550°E 22.10' 12" Red Pine P.S 21559 tag
 Corner falls in woods at Northwesternly corner of recent clearcut area



Signed by James A. Beck
 Surveyor's Michigan License No. 21559

Date 12-18-1999