

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,

LAND CORNER REMONUMENTATION

LIBER 335 PAGE 213

DEC 29 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
PRESQUE ISLE

Located in: BISMARCK TWP. Corner Code #: C-4 ✓

T 34N R 4E  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

Recorded Dec 20, 1999  
At 10:30 o'clock A M  
Janet M. Lamb  
Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, James A. Beck, in a field survey on Nov 9-11, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7	8			9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-4 1/4 Corner common to Sections 7 and 8  
1856 G.L.O. by Alfred Millerd: "Set of Section post"  
Spruce 11 S50E 3  
Spruce 10 N72W 73

PA 74 Certificate by Carl Kliskila PS 33981; "reestablished the E 1/4 C-4 Sec 7 midway on line" dated May 29, 1997; between found NE and SE corners of Section 7"; Set D.N.R. Mon.  
24" R Pine S54°E 62.30'; 12" Oak N63°W 91.22';  
20" Oak N20°W 106.04'; N-S trail road 300' +/- East

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4 November 11, 1999 Remonumentation by James A. Beck P.S. 21559 Found DNR Monument  
24" R Pine S54°E 62.30'  
12" Oak N63°W 91.22'; 20" Oak N20°W 106.04'

Chairman James A. Beck  
Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 November 11, 1999 Remonumentation by James A. Beck P.S. 21559  
DNR Monument; 24" R Pine S54°E 62.30'  
12" Oak N63°W 91.22'; 20" Oak N20°W 106.04'  
N60°E 54.46' 21559 tag in 3" Jack Pine  
Corner falls in sparsely wooded area 300' +/- West of trail road



Signed by James A. Beck  
Surveyor's Michigan License No. 21559

Date 12-18-1999