

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,

LAND CORNER REMONUMENTATION

LIBER 335 PAGE 214

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
PRESQUE ISLE

	Located In:	Corner Code #
	BISMARCK TWP.	C-5 ✓
1. Public Land Survey	T 34 N R 4 E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Dec. 20, 1999
At 10:30 o'clock A M
Janet M. Lamb
Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Nov 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-5 1856 G.L.O. by Alfred Millerd
"Set post corner of Sections 7, 8, 17 & 18"
Y. Pine 20 S72E 47'; Y. Pine 18 N63W 105'
PA 74 Certificate by Larry G. Bearegard RLS 18654
"Found 1 1/2" pipe in line with fence South" Dated July 25,
1979; SASW 8" J. Pine 27.27'; N35W 8" Jack Pine 25.40'

PA 74 Certificate by Carl Kiskila PS 33981 Dated May 29, 1997
Kiskila "found and accepted 1 1/2" Pipe as witnessed by
Larry Bearegard", set carsonite post; 22" R. Pine N13°E
25.90'; 8" Oak S07°E 32.41'; 7" J. Pine S63°W 48.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5 November 12, 1999 Remonumentation by James A. Beck P.S. 21559
Found 1 1/2" pipe with 33981 cap inside
22" R. Pine N13°E 25.90' (spike)
8" Oak S07°E 32.41' (spike)
7" J. Pine S63°W 48.71' (spike)
10" J. Pine N28°W 25.7' (spike)

Ratified by Peer Group
in accordance with P.A. 345
Chairman William J. [Signature]
Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5
1 1/2" pipe with 33981 cap inside; 22" R. Pine N13°E 25.90' (spike)
8" Oak S07°E 32.41' (spike) 7" J. Pine S63°W 48.71' (spike)
10" J. Pine N28°W 25.7' (spike)
N20°E 35.5' 21559 tag in 12" Jack Pine; Corner falls on side of hill in mixed timber area
lying Easterly of and visable from Richard Lake Road



Signed by James A. Beck
Surveyor's Michigan License No. 21559

Date 12-18-1999