

198

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN
LAND CORNER REMONUMENTATION LIBER 335 PAGE 215

DEC 29 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
For corners in
PRESQUE ISLE

	Located In:	Corner Code #
	BISMARCK TWP.	C-6 ✓
1. Public Land Survey	T 34 NR 4E	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Recorded Dec 20, 1999
At 10:30 o'clock A M
Janet M. Lamb
Reg. of Deeds, Presque Isle Co., MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Dec 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18	17		16		15		14		13			
7													
8	19	20		21		22		23		24			
9													
10	30	29		28		27		26		25			
11													
12	31	32		33		34		35		36			
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


C-6	1856 G.L.O. by Alfred Millerd "Set of Sec. post" Tamarack 6 S36W 38; Tamarack 6 N50E 13	December 15, 1980 P.A. 74 Certificate by Delmer E. Porter RLS 15410 "Found nothing, Set 1/2" Rod by Single Proportion" S85°W 18.26' 8"W. Pine; S58°E 53.41' 14" Y. Pine S29°E 59.84' 12"W. Pine; Swamp edge 40-60' North
-----	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6	December 7, 1999 Remonumentation by James A. Beck P.S. 21559; Found 1/2" Rod and 15410 (Delmer Porter) cap and all of Porter's witnesses: S85°W 18.26' 8"W. Pine; S58°E 53.41' 14" Y. Pine S29°E 59.84' 12"W. Pine Swamp edge 40-60' North	Witnesses (group) in accordance with P.A. 345 Chairman <u>Norman J. Ode</u> Date <u>12/14/99</u>
-----	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 December 7, 1999 Remonumentation by James A. Beck P.S. 21559
1/2" Rod and 15410 (Delmer Porter) cap
S85°W 18.26' 8"W. Pine; S58°E 53.41' 14" Y. Pine;
S29°E 59.84' 12"W. Pine; Swamp edge 40-60' North
set 2 additional witnesses
N31°E 31.90' P.S. 21559 cap in 22" W. Pine @
South 4.62', P.S. 21559 tag in 8" Maple. Corner falls in wooded area South of strip of rye field



Signed by James A. Beck Date 12-18-1999
Surveyor's Michigan License No. 21559