

**1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,
LAND CORNER REMONUMENTATION**

LIBER **335** PAGE **217**

DEC 29 1999

SECTION _____

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
PRESQUE ISLE

	Located In:	Corner Code #
	BISMARCK TWP.	C-9 ✓
1. Public Land Survey	T <u>34</u> N R <u>4</u> E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Dec 20, 1999
At 10:30 o'clock A M
Janet M. Lamb
Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Dec 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		⊕										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-9 1856 G.L.O. by Alfred Millerd July 21, 1981; P.A. 74 Certificate by Ronald Bischer PS 2242B;
"Set post Corner Secs 19, 20, 29 & 30" "Found 2 O.B.T. Stumps" (set) 1/2" rod and cap 535°W 37.66' 10" Oak;
Y. Pine 20 N60E 28; W. Pine 20 S60W 23 506°W 4.95' 4" Oak 515°E 44.05' 10" Oak
March 25, 1994 P.A. 74 Certificate by Norman J. Quaine PS 3398A
"Fd 1" Pipe by Square Post"; 538°W 37.94' 12" Oak
516°W 5.17' 8" Oak; 509°E 44.14' 14" Oak; NOB°E 37.92'
6" Aspen

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 December 2, 1999; Remonumentation by James A. Beck P.S. 21559
Found 1" Pipe, found remnants of stumps referred to in Bischer's 1981 P.A. 74 recordation.
538°W 37.94' 12" Oak; 516°W 5.17' 8" Oak
509°E 44.14' 14" Oak; NOB°E 37.92' 6" Aspen

Ratified by Peer Group
in accordance with P.A. 845
Chairman *Norman J. Quaine*
Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9 December 2, 1999 Remonumentation by James A. Beck P.S. 21559
1/2" iron rod with P.S. 21559 cap inside 1" pipe
538°W 37.94' 12" Oak; 516°W 5.17' 8" Oak
509°E 44.14' 14" Oak; NOB°E 37.92' 6" Aspen
Set 1 additional witness
576°E 60.05', 21559 tag in 6" W. Pine



Signed by *James A. Beck*
Surveyor's Michigan License No. 21559

Date 12-18-1999