

**1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,
LAND CORNER REMONUMENTATION**

LIBER 335 PAGE 218

DEC 29 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION
For corners in
PRESQUE ISLE

	Located In:	Corner Code #
	BISMARCK TWP.	C-10
1. Public Land Survey	T 34 N R 4 E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded Dec 20, 1999
At 10:30 o'clock A M
Janet M. Lamb
Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James A. Beck, in a field survey on Nov 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-10	1856 G.L.O. by Alfred Millerd "Set qr. Sec. post" Y. Pine 20 S42W 30; W. Pine 20 East 13	July 10, 1990 Reference by Porters Survey 1/2" rod & Cap S 05° E 56.04' 14" Red Pine S 44° W 53.75' 12" Oak N 37° W 23.00' 12" Twin Aspen
------	--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10 November 30, 1999 Remonumentation by James A. Beck P.S. 21559
found 1/2" iron rod and P.S. 15410 cap and all witnesses and reference tags from Porter's record
S 05° E 56.04' 14" Red Pine
S 44° W 53.75' 12" Oak
N 37° W 23.00' 12" Twin Aspen

Checked by Peer Group
in accordance with P.A. 345
Chairman Norman J. Olson
Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10 November 30, 1999; Remonumentation by James A. Beck P.S. 21559
1/2" iron rod and P.S. 15410 cap
S 05° E 56.04' 14" Red Pine; S 44° W 53.75' 12" Oak
N 37° W 23.00' 12" Twin Aspen; set 2 additional witnesses:
S 51° E 53.08' 3" W. Pine P.S. 21559 tag
N 23° W 45.85' 8" W. Pine P.S. 21559 tag



Signed by James A. Beck
Surveyor's Michigan License No. 21559

Date 12-18-1999