

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,

LAND CORNER REMONUMENTATION

LIBER 335 PAGE 223

DEC 29 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
PRESQUE ISLE

(County)

Located in: **BISMARCK TWP.** Corner Code # **C-13** ✓

1. Public Land Survey T 34R4E
 T R
 T R
 T R

2. Property Controlling in Section S T R
 S T R

3. Miscellaneous Property in Sec. S T R
 S T R

Recorded Dec 20, 1999
 At 10:30 o'clock A M
Janet M. Lamb
 Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James A. Beck, in a sold survey on Nov 22, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	19		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 1840 G.L.O. by John Hodgeson
 (Twp. Boundary): "Set post Corner Sections 31 and 32" Birch 12 N.25E 28; Birch 10 N16W 22
 Circa 1940 + from Volume "Established Section Corners" on File in Presque Isle County Register of Deeds Office by G.F. DeLaMater RLS; 1/2" x 48" bar in cor; Y. Pine 12 N18W 59.6; W. Pine 3 55.6W 36.2; W. Pine 3 N49E 33.3

June 1964 From Volume "Established Section Corners" on File in Presque Isle County Register of Deeds Office By Orlando Doyle PS 7319 monument and references same as G.F. DeLaMater recordation above right
 June 29, 1975 P.A. 74 Certificate by Delmer E. Porter RLS 15410 monument and references same as G.F. DeLaMater recordation above
 Feb 16, 1976 P.A. 74 Certificate by Delmer E. Porter RLS 15410, "Fd. 1/2" Rod by 3"x3" Post; N18°W 60.26' 15"N. Pine; East 55.64' 14"W. Pine
 550°E 51.36' 10"N. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

C-13 November 22, 1999 Remonumentation by James A. Beck P.s. 21559 found 1/2" iron bar 1' +/- South of 3"x 3" post and following old witnesses:
 N12°W 60.33' 18" Norway
 550°E 51.36' 12" N. Pine
 East 55.50' 16" W. Pine

Chairman William J. Bevan
 Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 November 22, 1999 Remonumentation by James A. Beck P.s. 21559
 1/2" iron bar with P.S. 21559 cap 1' +/- South of 3"x 3" post
 N12°W 60.33' P.S. 21559 tag in 18" Norway
 N38°W 53.02' P.S. 21559 tag in 10" N. Pine
 550°E 51.36' P.S. 21559 tag in 12" N. Pine
 East 55.50' P.S. 21559 tag in 16" W. Pine



Signed by James A. Beck
 Surveyor's Michigan License No. 21559

Date 12-18-1999