

1999 PRESQUE ISLE COUNTY, STATE OF MICHIGAN,

LAND CORNER REMONUMENTATION

LIBER 335 PAGE 225

DEC 29 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
PRESQUE ISLE

Located in: **BISMARCK TWP.** Corner Code # **D-3** ✓
 1. Public Land Survey T 34R4E
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

Recorded Dec. 20, 1999
 At 10:30 o'clock A. M
Janet M. Lamb
 Reg. of Deeds Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James A. Beck, in a field survey on Dec 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	H
1													
2	6		5		4		3		2		1		
3				0									
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-3 1856 G.L.O. by Alfred Millerd; "Set quarter Section post"; Spruce Pine 6 NAOE 216; Spruce Pine 11 S2TW 30

April 16, 1992 PA 74 Certificate by Norman J. Quaine P.S. 33984 No corner evidence found, set corner by single proportion"; 1/2" rod and cap #15410; S22°W 49.00 4" Balsam; N74°W 85.94' 8" Red Pine
 S71°E 54.32' 5" Red Pine; S66°E 58.38' 5" Red Pine.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-3 December 1, 1999 Remonumentation by James A. Beck P.S. 21559; Found 1/2" iron rod and P.S. 15410 cap and all witness trees and tags from last recording
 S22°W 49.00 4" Balsam (dead); N74°W 85.94' 10" Red Pine
 S71°E 54.32' 8" Red Pine; S66°E 58.38' 8" Red Pine

by _____ Group
 in accordance with P.A. 345
 Chairman Norman J. Quaine
 Date 12/14/99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-3 December 1, 1999 Remonumentation by James A. Beck P.S. 21559
 1/2" iron rod and P.S. 15410 cap
 S22°W 49.00 4" Balsam (dead); N74°W 85.94' 10" Red Pine
 S71°E 54.32' 8" Red Pine; S66°E 58.38' 8" Red Pine
 S47°W 43.55' P.S. 21559 tag in 4" J. Pine



Signed by James A. Beck
 Surveyor's Michigan License No. 21559

Date 12-18-1999