

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields: Presque Isle (County), Located In, Corner Code #, 1. Public Land Survey, 2. Property Controlling in Section, 3. Miscellaneous Property in Sec.

Recorder stamp: Recorded Dec. 16, 1999 At 11:30 o'clock A.M. Janet M. Lamb Reg. of Deeds, Presque Isle Co. MI Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Ronald Bischer in a field survey on Aug. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column E and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

1856 GLO Notes
N25° E 31 lks 10" W. Birch
S30° W 30 lks 8" Cedar
Aug. 1, 1980 Danny Bongiovanni #24586
5/8" bar & cap
N40° W 18.62' 4" Spruce
S10° W 60.30' 10" Tamarack

March 25, 1994 Ronald Bischer
5/8" bar with cap #24586
N40° W 18.62' 7" Balsam
N06° E 43.80' 7" Maple
N76° E 50.45' 10" Maple
S06° W 60.30' 12" Balsam

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9
Aug. 20, 1999 Presque Isle County Remonumentation
Ronald Bischer #22428
found 5/8" bar with cap #24586
found 4 witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9
5/8" bar and cap #24586
N36° W 18.62' 7" balsam
N10° E 43.80' 8" maple
N81° E 50.45' 12" Maple
S51° W 38.95' 8" Balsam
S10° W 60.05' 13" Balsam

Ratified by Peer Group
in accordance with P.A. 345
Chairman [Signature]
Date 11/30/99



Signed by Ronald B. Bischer
Surveyor's Michigan License No. 22428

Date 12-13-99