

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>34</u> N <u>4</u> E	<u>E-3</u> ✓
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Recorded Dec. 16, 1999
 At 11:30 o'clock A.M
Janet M. Lamb
 Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald Bischer, in a field survey on Aug. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3						●							
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-3
 1856 GLO Notes
 N55°W 65 lks 12" Tamarack
 S05°E 16 lks 5" Tamarack
 S88°W 1.1 chns stream

3-19-91 Norman Quaine #33984
 1/2" rod and cap #15410
 set by s. P. stream crossing 72'
 west of position
 North 20.20' 12" Maple
 N50°W 20.82' 6" Maple
 S38°E 22.30' 10" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-3
 Aug. 20, 1999 Presque Isle County Remonumentation
 Ronald Bischer #22428
 found 1/2" rod and cap #15410
 found three witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-3
 1/2" rod and cap #15410
 N10°E 20.20' 9" Maple
 S32°E 22.30' 12" Maple
 N50°W 20.82' 8" Maple
 S60°W 13.51' 7" Balsam

Ratified by Peer Group
 in accordance with P.A. 345
 Chairman Norman J. Quaine
 Date 11/30/99



Signed by Ronald R. Bischer
 Surveyor's Michigan License No. 22428

Date 12-13-99