

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34R 4E F-7 ✓

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Recorded Dec. 16, 1999
At 11:30 o'clock A.M.
Janet M. Lamb
Reg. of Deeds, Presque Isle Co. MI

Register of Deeds Stamp & File Number

I, Ronald Bischer, in a field survey on Aug. 20, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

F-7
1856 GLO Notes
N15°E 50 lks 6" Aspen
S43°W 5 lks 5" Spruce pine
Feb 25, 1986 Delmer Porter #15410
set 1/2" rod by sp
N22°E 11.40' 5" Oak
S08°W 22.43' 8" Oak
S31°W 24.26' 4" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7
Aug. 20, 1999 Presque Isle Remonumentation
Ronald Bischer #22428
found 1/2" rod and cap #15410
found three witnesses

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7
1/2" rod and cap #15410
S08°W 22.57' 10" Oak
S32°W 24.45' 6" Maple
N21°E 11.31' 9" Maple
N62°E 34.19' 9" Oak

Ratified by Peer Group
in accordance with P.A. 345
Chairman Norman J. Quinn
Date 11/30/99



Signed by Ronald R. Bischer
Surveyor's Michigan License No. 22428

Date 12-13-99