

**SURVEY & REMONUMENTATION**

JAN 14 1999

LIBER 329 PAGE 873

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

- |                                    |   |            |           |            |
|------------------------------------|---|------------|-----------|------------|
| 1. Public Land Survey              | T | <u>34R</u> | <u>4E</u> | <u>G-1</u> |
|                                    | T | _____      | _____     | _____      |
|                                    | T | _____      | _____     | _____      |
|                                    | T | _____      | _____     | _____      |
| 2. Property Controlling in Section | S | _____      | _____     | _____      |
|                                    | S | _____      | _____     | _____      |
| 3. Miscellaneous Property in Sec.  | S | _____      | _____     | _____      |
|                                    | S | _____      | _____     | _____      |

PRESQUE ISLE COUNTY  
RECORDED

98 DEC 17 PM 4:25

*Janet M. Lamb*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Delmer E. Porter in a field survey on July 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- |  |                           |
|--|---------------------------|
| G-1 GLO Notes - Set Post                 | GLO NOTES - June 26, 1856 |
| Aspen 6 N16°W 37                         | Hemlock 12 S45W 22 Links  |
| Hemlock 10 S75°E 37                      | Hemlock 8 S45E 30 Links   |
| Old Corner 266 Links & 163' West Effaced |                           |
| Pine 36 N83E 78                          |                           |
| Birch 4 N35W 16                          |                           |
| N1°46'W 1.94 Enter Swampy Thicket E & W  |                           |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-1 1/2" Rod & Cap #15410  
N38°E 23.05' 24" N. Pine  
S45°E 41.60' 16" Pine  
S30°E 52.52' 16" N. Pine  
S08°W 38.16' 12" Spruce

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-1 1/2" Rod & Cap #15410  
N19°E 21.64' 4" spruce  
N34°W 39.05' 4" Maple  
N48°E 6.70' 4" Maple  
N63°E 11.30' 5" Maple



Ratified by Peer Group in accordance with P.A. 345

Chairman *Anthony J. Quinn*

Date 12/17/98

Signed by *Delmer E. Porter*  
Surveyor's Michigan License No. #15410

Date 12/09/98