

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Presque Isle</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T34N R4E	G-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

PRESQUE ISLE COUNTY
RECORDED

98 DEC 17 PM 4:25

Janet M. Lamb
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Delmer E. Porter in a field survey on July 2, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-5 GLO NOTES
June 26th 1856
Set Post 9,10,15 & 16
Cedar 10 S40W 15 Links
Cedar 7 N65E 23 Links

SURVEY &
REMONUMENTATION

JAN 14 1999


SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 Set 1/2" Rod & Cap At Fence N-S
N22°W 17.19' 4" Balsam
N43°E 22.09' 6" Balsam
S80°E 14.02' 6" Balsam

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-5 1/2" Rod & Cap #15410
N22°W 17.19' 4" Balsam
N43°E 22.09' 6" Balsam
S80°E 14.02' 6" Balsam
S65°W 10.26' 5" Balsam
S24°W 29.73' 5" Balsam
Corner at N-S Fence



Ratified by Peer Group
in accordance with P.A. 345

Chairman *Norman J. Quinn*

Date 12/17/98

Signed by *Delmer E. Porter*

Date Dec 9, 1998

Surveyor's Michigan License No. #15410