

2512

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Presque Isle  
(County)

Located In:

Corner Code #

1. Public Land Survey

T 34N R 4E G-8

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

PRESQUE ISLE COUNTY  
RECORDED  
98 DEC 17 PM 4:26  
*Jane M. Lamb*  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, Delmer E. Porter in a field survey on Jan. 14, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-8 GLO NOTES
- Set Quarter Sec Post
- Tamarac 4 S75E 8 Links
- Tamarac 5 N27W 6 Links

SURVEY & REMONUMENTATION

JAN 14 1999


SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-8 1/2" X 24" Rerod
- N73°E 24.12' 12" Balsam
- S35°E 48.62' 4" Maple
- S41°W 23.42' 8" Tw. Maple

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-8 1/2" Rod & Cap #15410
- N14°W 32.13' 3" Elm
- N73°E 24.12' 12" Balsam
- N87°E 23.41' 4" Balsam
- S53°E 48.62' 4" Maple
- S41°W 23.42' 8" Twin Maple
- N79°W 38.28' 8" Balsam



Ratified by Peer Group  
in accordance with P.A. 345  
Chairman *Norman J. Quinn*  
Date 12/17/98

Signed by Delmer E. Porter

Surveyor's Michigan License No. #15410

Date Dec 9, 1998